

5/18

<b>DART AEROSPACE LTD</b>	<b>Work Order:</b>	<b>23013</b>
<b>Description:</b> Placard	<b>Part Number:</b>	<b>D3301-3</b>
<b>Dwg:</b> D3301 Rev. A	<b>Qty:</b>	<b>10</b>
		Page 1 of 1

Step	Location	Procedure	By	Date	Qty
1	DC	Issue Traveler	PL	05.04.13	10
2	PG	Issue P/O: <u>7024890</u> Make as per Dwg D3301 Red letters (0.22" min. height) on white adhesive back Possible Manufacture: From 3M 7 mil masking film # 8522CP or Avery IPM # 2031 Possible Supplier: Studio Lettrage <b>Material release note is required</b>	U.	05.04.13	10
3	RG	Receive and Inspect for transit damage <b>Enure material release note is attached</b>	CL	05/04/21	10
4	QC6	Inspect dimensions as per Dwg D3301	U.	05.04.28	10
5	ST	Identify and Stock	CL	05/04/26	10
6	AC	Cost / part <u>6.78</u>	Sue	05.04.27	10
7	DC	Close W/O <u>7.46</u> Inspect Level 21	PL	05.04.29	10

Rev	Date	Change	Revised By	Approved
A	04.09.02	New issue	KJ/JLM	

**RELEASED**  
PL/04.09.02

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Mfg / Design Mgr	Approval QC Inspector

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Design Mgr	Approval QC Inspector
			Initial Design Mgr	Action Description Design Mgr	Sign & Date			

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_


NOTE: Date & initial all entries

QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_



DESIGN [Signature]	DRAWN BY [Signature]	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED [Signature]	APPROVED [Signature]	DRAWING NO. D3301	REV. A SHEET 2 OF 2
DATE 04.07.06		TITLE PLACARD	SCALE 1:1

RELEASED  
04.09.04 [Signature]



D3301-3 PLACARD

D3301-3 DECAL

1) MATERIAL:

RED LETTERS ON WHITE ADHESIVE BACK

MANUFACTURED FROM 3M 7 MIL MASKING FILM #8522CP OR AVERY IPM # 2031

MAXIMUM SIZE IS 4.0" WIDE x 1.0" HIGH

2) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED


3) ALL DIMENSIONS ARE IN INCHES

SHOP COPY  
RETURN TO  
DRAWING  
UNLESS OTHERWISE NOTED  
SUCH AS AMENDMENT  
WITHOUT NOTICE  
WORK ORDER  
NO. 23013



DESIGN RT	DRAWN BY RT	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED [Signature]	APPROVED [Signature]	DRAWING NO. D3301	REV. A SHEET 1 OF 2
DATE 04.07.06		TITLE PLACARD	SCALE 1:1
A	04.07.06	NEW ISSUE	

RELEASED  
04.07.06 [Signature]



D3301-1 PLACARD

D3301-1 DECAL

1) MATERIAL:

RED LETTERS ON WHITE ADHESIVE BACK

MANUFACTURED FROM 3M 7 MIL MASKING FILM #8522CP OR AVERY IPM # 2031

MAXIMUM SIZE IS 5.0" WIDE x 2.0" HIGH

2) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED

3) ALL DIMENSIONS ARE IN INCHES

SHOP COPY  
TO  
COPY  
COPY  
ORDER  
NO. 23013

Copyright © 2004 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

# Job Costing Report

Dart Aerospace Ltd.  
Hawkesbury

Apr 12, 2005  
02:25 pm

Work Order No : 0023013  
Project Name : D3301-3  
Project For : WK518  
Work Order Type : Main  
Main WO Number :  
House Part Number : D3301-3  
Description : PLACARD  
Manufactured : Yes  
Amount Req'd : 10  
Amount Done : 0  
Start Date : 04-12-05  
Est Finish Date : 04-30-05  
Act Finish Date :  
Drawings Req'd : No  
Ok for Approval :  
Approval Rec'd :

Department Code:  
Burden Flags : NNNNNNNN  
WO Status : Open  
Invoice State : Not Invoiced  
Invoice Date :  
Invoice Number :  
Invoice Amount : 0.00  
Order Entry No :  
OE Value : 0.00  
Est Mark Up : 0.000%  
Actual Mark Up : 0.000%  
\$0 Posted to Finished Goods

	Estimated	Actual	Var. %	Posted	To Post
Material Cost :	0.00	0.00	0.00	0.00	0.00
Engineering Hours :	0.00	0.00	0.00		
Engineering Cost :	0.00	0.00	0.00	0.00	0.00
Production Hours :	0.00	0.00	0.00		
Production Cost :	0.00	0.00	0.00	0.00	0.00
Packaging Hours :	0.00	0.00	0.00		
Packaging Cost :	0.00	0.00	0.00	0.00	0.00
OverHead Hours :	0.00	0.00	0.00		
OverHead Cost :	0.00	0.00	0.00	0.00	0.00
CNC Hours :	0.00	0.00	0.00		
CNC :	0.00	0.00	0.00	0.00	0.00
Misc. Hours :	0.00	0.00	0.00		
Misc. :	0.00	0.00	0.00	0.00	0.00
Burden :	0.00	0.00	0.00		
Total Cost :	0.00	0.00	0.00		
Mark up :	0.000	0.000			
Selling Cost :	0.00	0.00			

	Estimated	Actual
Labour Hrs/Amount Done :	0.00	0.00
Profits/(Loss) :	0.00	0.00



# Scotchcal™

## Opaque Imaging Media 8522

### Description

This media is specially formulated to dry quickly after printing. Production of outdoor weatherable and long-term indoor durable graphics is now easier than ever. Its changeable adhesive allows easy removal for up to one year.

### Advantages

- Optimized for use with selected Epson Stylus Pro printers and Epson Archival inks.
- Optimized for use with selected HP DesignJet Printers and HP DesignJet Ink System UV or HP83UV Color Ink System
- For making opaque, laminated graphics that are outdoor weatherable and long-term indoor durable
- Media:
  - For opaque (reflective) graphics
  - Changeable, easy to remove from warranted substrates up to 1 year later
  - Dries quickly after printing so the overlamine can be applied almost immediately
  - Low slippage paper liner for superior tiling
- Overlaminates:
  - Provide additional UV (ultraviolet) and physical protection for making weatherable finished graphics
  - Available in luster and matte gloss
  - Adhesive allows for heat-assisted or cold-temperature lamination

### Applications and Uses

3M™ Scotchcal™ Changeable Opaque Imaging Media 8522 is intended only for ink jet printing and for use with the listed Compatible Products and Equipment and the following applications. Any other application is NOT warranted by 3M or covered by the worldwide 3M™ MCS™ Warranty unless 3M gives its prior written approval for the application.

- First surface images (the image is on top of the film) for opaque posters and signs, including:
  - Graphics for vans, personal vehicles, trucks and buses
  - Novelty posters
  - Retail and point-of-purchase displays
  - Information graphics such as maps and directories
  - Entertainment promotions in museums, zoos, parks, theatres, sports venues
  - Education and presentation graphics

### Product Bulletin 8522

Release F, Effective January 2003  
Black bar in margin indicates a change

- Legal and courtroom exhibits

- For flat or simple curved surfaces, with or without rivets, used in vertical ( $\pm 10^\circ$ ) applications

### Limitations of End Uses

The following uses and applications are specifically NOT warranted.

- Fleet applications in areas that use salt for winter road maintenance
- Application to non-warranted substrates, including wall-board
- Applications subjected to gasoline vapors or spills
- Application to corrugated or highly irregular surfaces or sharply raised areas
- Graphics applied to stainless steel, including stainless steel vehicles
- On flat surfaces with rivets, tenting of 4 to 10 mm around rivets may be expected; rivets may be cut around to eliminate tenting.

Note: Standard ink jet technology is water based. Water-based chemistry is susceptible to the extremes of heat and humidity. This is a factor in most product constructions on the market. Read the Fabrication, Shelf Life and Storage sections in this bulletin. Staying in the middle of these ranges always provides optimum performance.

### Compatible Products and Equipment

#### Thermal Ink Jet Printing Systems

- Epson Stylus Pro 9500, Stylus Pro 10000 printer
  - Epson Archival Inks
- Epson Stylus Pro 10600 printer
  - Epson Archival Inks
- HP DesignJet Printers 2000 and 3000 series
  - HP DesignJet Ink System UV (pigment-based ink)
- HP DesignJet Printers 5000 series
  - HP83UV Color Ink System

#### Overlaminates (required)

- 3M™ Luster Overlamine 8519 (semi-gloss)
- 3M™ Matte Overlamine 8520

Note: For the full product names of the 3M products listed on this page, please see page 1.

### Warranted Substrates

Media 8522 is warranted for use on the following rigid substrates.

Some substrates may "out-gas", resulting in tiny bubbles throughout the surface of the graphic. For maximum performance, be sure the substrate you select is properly cleaned and prepared as recommended by the manufacturer. See Instruction Bulletin 5.1 for additional information.

- Alodine (anodized aluminum)
- Automotive panels (automotive painted steel)
- Fruehauf (painted aluminum)
- FRP (fiberglass reinforced plywood)
- Glass
- Imron® (polyurethane-painted metal panel)
- Acrylic
- Sintra™ board

### Test and Approve Non-warranted Substrates Before Use

Media 8522 is not warranted for any substrate other than those listed above. If you want to use it for other substrates, 3M recommends that you test and approve the media for both adhesion and removal characteristics.

## Characteristics

Characteristic	Description
Media	7 mil, white, opaque graphic film
Liner	Low-slippage, lay flat paper
Adhesive	Changeable, pressure sensitive
Thickness (media and adhesive)	7.5 to 8 mil (nominal)
Application substrates	See Warranted Substrates, above
Application surfaces	Flat or simple curved surfaces, with or without rivets, used in vertical ( $\pm 10^\circ$ ) applications (no corrugations)
Application temperature range	28° to 110°F (-2° to 43°C) (air and surface)
Roll sizes	36" x 45 feet (914 mm x 13.5 m) 54" x 45 feet (1372 mm x 13.5 m)

## How to Become a 3M Ink Jet Registered Fabricator

Only 3M Thermal Ink Jet Registered Fabricators are eligible to offer 3M MCS warranted graphics. In order to become certified, a fabricator must complete the requirements as specified in the 3M Ink Jet Graphics Registered Fabricator Reference Manual located on the 3M website at [www.scotchprint.com](http://www.scotchprint.com)

## Effective Performance Life

To obtain the warranty given below, the graphics must be made according to 3M's recommendations which are detailed in the Warranty and Limited Remedies on page 3. Also see the section, Removability.

### Warranted Durability

Media 8522 with Overlaminate 8519 or 8520	Epson Printers		HP Printers	
	Outdoor	Indoor	Outdoor	Indoor
Applied to Warranted Substrates	2 years	5 years	3 years	5 years

## Removability

Imaging media 8522 is removable from warranted substrates for 1 year without the aid of chemical strippers or accessories. Refer to Instruction Bulletin 4.23 for additional information.

## Fabrication


Graphics must be made according to 3M's recommendations which are detailed in the Warranty and Limited Remedies on page 3.

See Instruction Bulletin 4.23 for detailed fabrication, printing and mounting information.

## Graphic Construction Options

### Opaque (Reflective) Graphics

Opaque graphics made with imaging media 8522 require an overlaminate and an opaque substrate.




Note: For the full product names of the 3M products listed on this page, please see page 1.

## Shelf Life and Storage

- 3M™ Scotchcal™ Changeable Opaque Imaging Media 8522 has a shelf life of one year.
- Storage conditions (new and partially used rolls). For optimum performance, use the middle of these ranges:
  - Original packaging, including plastic wrap
  - Relative humidity of 20% to 80%
  - Temperature of 33° to 104°F (0° to 40°C)
  - Away from direct sunlight
- Do not stack unprotected rolls or lay sharp or heavy objects on them.

## Health and Safety

 **Caution**

When handling any chemical products, read the manufacturers' container labels and the Material Safety Data Sheets (MSDS) for important health, safety and environmental information.

To obtain MSDS sheets for 3M products:

- By fax, call 1-800-364-0768 in the US and Canada or 1-650-556-8417 for all other locations.
- Electronically, visit us at <http://www.3M.com/msds>.
- By mail, or in case of an emergency, call 1-800-364-3577 or 1-651-737-6501.

When using any equipment, always follow the manufacturers' instructions for safe operation.

## Warranty and Limited Remedies

### 3M™ MCS™ Warranty for Graphics Produced on HP DesignJet Printers and Epson Stylus Pro Printers

*The following is made in lieu of all other express or implied warranties, including any implied warranty of merchantability or fitness for a particular purpose:* We warrant graphics produced by a 3M Ink Jet Registered Fabricator made with imaging media 8522, printed on an approved HP thermal ink jet printer according to HP's recommendations or Epson Stylus Pro printer according to Epson's recommendations, overlaminated with 8519 or 8520, and applied to a Warranted Substrate according to 3M's recommendations. These



**Commercial Graphics Division**  
3M Center, Building 220-6W-06  
PO Box 33220  
St. Paul, MN 55133-3220 USA  
General Info. 1-800-374-6772  
Technical Info. 1-800-328-3908  
Fax 1-651-736-4233

Fax-on-Demand 1-800-364-0768 US/Canada or 1-651-732-6506 International  
Fax-on-Demand document: 4506  
[www.scotchprint.com](http://www.scotchprint.com)

**3M Canada**  
P.O. Box 5757  
London, Ontario  
Canada N6A 4T1  
1-800-265-1840  
Fax 519-452-6245

**3M México, S.A. de C.V.**  
Av. Santa Fe No. 55  
Col. Santa Fe, Del. Alvaro Obregón  
México, D.F. 01210  
52-55-52-70-04-00  
Fax 52-55-52-70-22-77

**3M Puerto Rico, Inc.**  
Puerto Rico Industrial Park  
P.O. Box 100  
Carolina, PR 00986-0100  
787-620-3000  
Fax 787-750-3035

graphics are covered against failure caused by ultraviolet light, temperature extremes, pollution, and other elements.

If a graphic fails to perform in accordance with 3M product specifications within this time frame, 3M will replace the materials at no charge. **These remedies are exclusive. In no case shall 3M be liable for any direct, indirect, or consequential damages, including any labor charges.**

## 3M Related Literature

Listed below is related 3M technical literature that may be of interest. You may view and print these Bulletins from our Web site at [www.scotchprint.com](http://www.scotchprint.com), or order them via our Fax-on-Demand (FOD) system. Call one of these phone numbers to order the desired bulletins, and specify the FOD document number provided in the chart.

United States or Canada: 1-800-364-0768  
International: 1-651-732-6506

Subject	Bulletin No.	FOD No.
<b>Product Bulletins</b>		
3M™ Scotchcal™ Overlamine 8519 and 8520	8519/8520	4524
<b>Instruction Bulletins</b>		
Making thermal ink jet graphics	4.23	6523
Application, substrate selection, preparation and substrate-specific application techniques	5.1	7001
<b>Warranties</b>		
<b>Worldwide 3M™ MCS™ Warranty Packet</b> <i>(includes all Commercial Graphics MCS Warranties)</i>		9503
Worldwide 3M™ MCS™ Warranty Overview-Folder		9504

*3M, Scotchcal and MCS are trademarks of 3M.  
Epson and Stylus Pro are trademarks of Epson.  
HP and DesignJet are tradenames of Hewlett Packard.  
Sintra is a trademark of Swiss Aluminum Ltd.  
Imron is a registered trademark of DuPont in the United States*

### Bulletin Change Summary

The Epson Stylus Pro Printers 9500, 10000 10600, and Epson Archival Inks have been added to this bulletin. Additional changes resulting from this addition are marked with black bars in the margin.